

Hirschfeld Backhoe & Pipeline

Longmont, CO

Project Size

1,680 sq ft

Construction

Type V-b

Contract Type

Negotiated

Facility Use

Commercial office

Description

Private offices, conference room, business office, break and reception areas

Completion

60 days

Pier & Beam
Permanent
Modular
Construction



When Hirschfeld Backhoe & Pipeline needed to relocate their main office to the company's Longmont storage location, Ramtech designed, manufactured, and installed a 1,680 square foot modular building using pier and beam permanent modular construction. The facility was pit set on a stem wall foundation that allowed for a grade level appearance with a storefront entry. The interior layout provides space for four private offices, conference room, large business office, and an adjoining break and reception area. The building utilizes stucco embossed HardiePanel exterior vertical siding, high rib steel roofing, and wall-mounted Bard HVAC units for heating and cooling. The interior is finished-out with vinyl covered gypsum walls and a combination of VCT and carpet flooring.

RAMTECH
Building Systems
800-568-9376
ramtechmodular.com